



## NOTICE ROAD WORK BID

The Town of Peshtigo, Marinette County, will be accepting bids for Hot Oil Chip Sealing and Spot Cold Mix Paver Wedging on various town roads. For specifications and project list

Contact Supervisor John Kowalski at 715-923-7891

Sealed Bids should be mailed or delivered to the Clerk at the Town Hall W2435 Old Peshtigo Rd, Marinette, WI, 54143. Office hours are 10:00 a.m. till 2:00 p.m. Bids are due by

7:00 pm on Tuesday August 16<sup>th</sup>, 2022. Bids will be opened during the meeting. Any questions should be in writing and will be shared with any prospective bidder.

The town reserves the right to reject any bid and accept the bid most advantageous to the town.

Clarence E Coble, Clerk  
Town of Peshtigo



**Town of Peshtigo – Marinette County  
2022 Road Project Bid Form**

Company Name: \_\_\_\_\_ Representative: \_\_\_\_\_

**4. Krause Rd #2 - Keller Rd to Strojny Rd - .51 mi by 18 ft**

Single Chip Seal                      5,500 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Cold Mix Paver Wedging              66 Ton - Per Ton \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total    \$ \_\_\_\_\_

**5. Krause Rd #3 - CTH B to change North of Oak Ridge Rd - 2.07 mi by 20 ft**

Single Chip Seal                      25,500 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Cold Mix Paver Wedging              242 Ton - Per Ton \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total    \$ \_\_\_\_\_

**6. Keller Rd - Krause Rd towards Little River Rd - 1.07 mi by 20 ft**

Single Chip Seal                      12,600 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Cold Mix Paver Wedging              22 Ton - Per Ton \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total    \$ \_\_\_\_\_

**7. Hale Rd - Harbor Rd towards Felmer Rd .66 mi by 20 ft**

Single Chip Seal                      7,900 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total    \$ \_\_\_\_\_

**Town of Peshtigo – Marinette County  
2022 Road Project Bid Form**

Company Name: \_\_\_\_\_ Representative: \_\_\_\_\_

**INDIVIDUAL Project with Subtotals:**

1. Madsen Rd – CTH B to Roosevelt Rd - 1.09 mi x 20 ft

Single Chip Seal                      12,900 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Cold Mix Paver Wedging              264 Ton - Per Ton \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total \$ \_\_\_\_\_

2. Heath Ln - CTH BB to Krause Rd - 1.11 mi by 20 ft

Single Chip Seal                      13,100 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Cold Mix Paver Wedging              220 Ton - Per Ton \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total \$ \_\_\_\_\_

3. Krause Rd #1 - CTH BB to Dahl Rd - 1.22 mi by 20 ft

Single Chip Seal                      14,500 SY - Per SY \$ \_\_\_\_\_ = \$ \_\_\_\_\_

Total \$ \_\_\_\_\_

# Town of Peshtigo – Marinette County 2022 Road Project Bid Form

- ❖ Bids are due on Tuesday August 16<sup>th</sup>, 2022 @ 7:00 pm
- ❖ Bids will be decided at the monthly town board meeting on Tuesday August 16<sup>th</sup>, 2022
- ❖ **A copy of this list must be filled out as-is and included with any bid to be considered**
  - Contractor must supply town with proof of insurance
- ❖ The Town reserves the right to accept or reject an or all bids

## **Hot Oil Chip Seal & Cold Mix Paver Wedging**

Contractor shall supply all labor, materials and equipment to sign work zone. Immediately before applying the liquid asphalt, clean the existing surface with a power broom to remove dirt, clay or other debris.

PG 58-28 5% Cut Back Liquid Asphalt blended at a State of Wisconsin and ASSHTO certified liquid asphalt production facility: furnished, heated to 350°F and applied in a single pass up to 24 feet wide.

Cover aggregate needs to be a 100% fractured washed chip

Cover Aggregate Type: \_\_\_\_\_

Cover Aggregate Size: \_\_\_\_\_

Company Name: \_\_\_\_\_

Representative: \_\_\_\_\_

**TOTAL (1-7): \$ \_\_\_\_\_**

**Town of Peshtigo – Marinette County  
2022 Road Project Bid Form**

Company Name: \_\_\_\_\_ Representative: \_\_\_\_\_

**INDIVIDUAL Project Totals:**

- |  |                               |
|--|-------------------------------|
| 1. Madsen Rd - 1.09 mi by 20 ft:<br>CTH B to Roosevelt Rd                                | <b>Project Total \$</b> _____ |
| 2. Heath Ln - 1.11 mi by 20 ft:<br>CTH BB to Krause Rd                                   | <b>Project Total \$</b> _____ |
| 3. Krause Rd #1 – 1.22 mi by 20 ft:<br>CTH BB to Dahl Rd                                 | <b>Project Total \$</b> _____ |
| 4. Krause Rd #2 – .51 mi by 18 ft:<br>Keller Rd to Strojny Rd                            | <b>Project Total \$</b> _____ |
| 5. Krause Rd #1 – 2.07 mi by 20 ft:<br>CTH B to pavement change North<br>of Oak Ridge Rd | <b>Project Total \$</b> _____ |
| 6. Keller Rd – 1.07 mi by 20 ft:<br>Krause Rd towards Little River Rd                    | <b>Project Total \$</b> _____ |
| 7. Hale Rd – .66 mi by 20 ft:<br>Harbor Rd towards Felmer Rd                             | <b>Project Total \$</b> _____ |